

The Islamia University of Bahawalpur

Renovation of Multi Purpose Room in Main Auditorium Building at Baghdad-ul-Jadeed Campus

MRS Jul-Dec, 2017

No	Description	Quantity	Rate	Unit	Amount
Civil Work (Non-Schedule)					
1	Providing & laying Floor/Dado tile 8"x1 meter (Wooden texture) wooden color China i/c 05% wastage laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 as approved by Engineer Incharge.	1073.25		Sft	Per Sft -
2	Providing & fixing wall paper best quality on walls as per approved design, colour and quality complete in all respect as approved by the Engineer Incharge	1212.75		Sft	Per Sft -
3	Providing & fixing deodar wooden glazed door 2" thick 4" frame with bottom rail 8" thick & middle & top rail 6" thick i/c door lock, door closer, hinges best quality tower bolt, specials wooden polishing complete in all respect as approved colour & design and sample and as directed by the Engineer Incharge	38.50		Sft	Per Sft -
4	1.5" thick with misty glass i/c deodar wood frame 2" thick & special wooden polishing complete in all respect as approved colour & design and sample as as directed by the Engineer Incharge.	120.00		Sft	Per Sft -
				Total	-