

E-TENDERING NOTICE

The Islamia University of Bahawalpur, M&R Division, intends to tender out the following schemes through E-Tendering.

All Contractors who are registered with the Pakistan Engineering Council (PEC) in the relevant category or above can participate in the open E-Tendering System. Procurement procedure strictly be adopted in accordance with PPRA Rules 2014 (with up-to-date amendments). Contractors can participate in E-Tendering after fulfilling the following terms & conditions:

- i. Contractors may register their firms on the website <https://punjab.eprocure.gov.pk> by submitting their requisite information.
- ii. After registration on the E-Tendering website <https://punjab.eprocure.gov.pk>, contractors of eligible categories may participate in E-Tendering.
- iii. Contractors / Bidders have to deposit Bid Security as per PPRA Clause 27 and upload scanned copies of Call Deposit Receipt (CDR) @ 5% of the estimated cost from any scheduled bank in favor of Executive Engineer (M), M&R Division, The Islamia University of Bahawalpur. Original CDR must be submitted to the Tender Opening Committee on tender opening date not later than 11:30 AM.
- iv. Contractors have to quote their rates online on item rate basis against each item of BOQ up to / before 11:00 AM. The rates quoted online by the contractors will be downloaded from the website and will be announced on the same date at 11:30 AM in the presence of participating firms / contractors and Tender Opening Committee in the office of the Executive Engineer (M), M&R Division, The Islamia University of Bahawalpur.
- v. All the contractors participating in E-Tendering will be bound to submit their Original CDRs with letter head and Valid PEC Licenses copy to the Tender Opening Committee on 29.05.2025 not later than 11:30 AM. In case of failure, the contractor will be declared as disqualified from the tender process in the presence of Tender Opening Committee. Further his case will be recommended to the Higher Authority for taking Strict Legal Action against the firm.
- vi. In case of holiday, next date of working day will be considered.
- vii. In case of false information, fake CDR, the contractor will be liable to disqualify as per PPRA Rules and will not be eligible to participate in upcoming tenders of IUB. Further his case will be forwarded to PEC and PPRA for initiation of Strict Legal Action.
- viii. Bid opening committee may reject all Bids or Proposals at any time prior to the acceptance of Bid or Proposal under PPRA Rule-35 (Rejection of Bids).
- ix. **Performance Guarantee:** The successful bidder will have to furnish a performance guarantee @ 10% of the contract amount as per PPRA Clause 56.

- x. The procuring agency shall, upon request, communicate to any bidder, the grounds for its rejection of all bids or proposals, but shall not be required to justify those grounds.
- xi. The contractor will have to quote Items Rates for each and every item of BOQ and work out the total amount in the BID on which he is willing to complete the work. In case any contractor quote Percentage Rates or left blank the BOQ's pages the same will be considered as "Non-responsive" and not to be included in the competition for determination of lowest evaluated bidder vide PPRA Circular dated 11.10.2024 & 29.11.2024 and in the light of General Directions for the Guidance of the Tender.

Sr. No.	Name of Work	Estimated Cost	Earnest Money @ 5%	T.S No. & Date	Time Limit	Opening date & Time
1	Construction of Partition with Brick Masonry at Law Department at Abbasia Campus	Rs. 31,96,185	Rs.1,59,800	1294/Engg, 15.04.2025	02- Months	29.05.2025 Closing time at 11:00 AM Opening time at 11:30 AM
2	Special Renovation of Toilet Blocks for Student (Male & Female) at Old Campus Bahawalnagar	Rs. 15,27,678	Rs. 76,380	1295/Engg, 15.04.2025	01- Month	



Executive Engineer (M)
The Islamia University of Bahawalpur
Baghdad ul Jadeed Campus,
Phone:062-9255459

The Islamia University of Bahawalpur

Construction of Partition with Brick Masonry at Law Department at Abbasia Campus

MRS, Jan to Jun 2025

No.	Ref.#	Description	Quantity	Unit Rate	Amount
1	7/5-i	Civil Work Pacca brick work in ground floor Ratio 1:3	916.12 Cft	% Cft	
2	11/9-b	Cement plaster 1:4 upto 20' (6.00 m) height:- b) ½" (13 mm) thick	6181.64 Sft	%Sft	
3	12/50	P/F 1-1/2" thick solid flush door comprising of 2.5mm thick Commercial ply compressed over 2.5mm thick commercial ply over 1" thick packing wood in style and rails under proper pressure i/c the cost of nails, tower bolt, handles, glue, sawing charges, Painting charges, sand papering and 3/8" thick matching wooden lipping as approved and directed by the Engineer Incharge.	343.00 Sft	P/Sft	
4	12/17 (iii)	Providing and fixing 2" wide MS/GI Chowkat singel /double rebate made of 16 SW/GMS sheet pressed/welded supported with M.S. flat 1 1/4"x1/8" i/c 6"long M.S. Flat 1"x1/8"hold fasts (6-Nos) welded/ screwed, punching of lock hole covered with MS Box,coating with an tirust paint including filling with cement sand mortar (1:8) and embedding hold fast incement concrete (1:2:4), complete in all respect as approved and directed by Engineer Incharge. (iii) 5.5 " wide	343.00 P/Sft	P/Sft	
5	11/22	Priming coat of chalk under distemper.	6181.64 Sft	%Sft	
6	13/31 a+b+b	Preparing surface and painting with emulsion paint:- 3 Coats New Surface	6181.64 Sft	%Sft	
7	12/60 b-(i)	P/F 3/4" dia heavy duty sliding bolt of specified material i/c the cost of hardware complete in all respect as approved and directed by the Engineer Incharge b) Brass (i) 10" (250 mm) long	16.00 Each	Each	
8	4/50	Dismantling glazed or encaustic tiles, etc	2150.92 Sft	% Sft	
9	4/48	Removing cement or lime plaster.	1490.58 Sft	% Sft	
10	4/19-c	Dismantling cement concrete 1:2:4 plain	58.86 Cft	% Cft	
11	6/5-f	Cement concrete plain including placing compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1: 2: 4	86.67 Cft	% Cft	
12	10/46 a-iii	Providing and laying superb quality Porcelain glazed tiles flooring of Master/ Stile brand or approved equivalent manufacturer of specified size in approved design,Color and Shade with adhesive/bond over 3/4"thick (1:3) cement plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respect as approved and directed by the Engineer Incharge a) Full body Glazed tiles (iii) 600mmx 600 mm	367.92 Sft	P/Sft	
13	13/31 a+b	Preparing surface and painting with emulsion paint:-old surface 2 coats	9456.72 Sft	% Sft	
14	13/4-c	Painting doors and windows, any type: old surface 2 coats	508.00 Sft	% Sft	

The Islamia University of Bahawalpur

Construction of Partition with Brick Masonry at Law Department at Abbasia Campus

MRS, Jan to Jun 2025

No.	Ref.#	Description	Quantity	Unit Rate	Amount
15	10/38	Providing and laying superb quality Porcelain glazed tiles of Master/ Stile brand or approved equivalent manufacturer, skirting/dado of specified size, Color and Shade with adhesive/ bond over 1/2"thick (1:2) cement plaster i/c the cost of matching sealer for finishing the joints, cutting grinding complete in all respect as approved and directed by the Engineer Incharge. Full body Glazed Tile 600mm x600 mm	240.25 Sft	P/Sft	
16	6/6	(a) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects:- (3) Type C (nominal mix 1: 2: 4)	24.00 Cft	P/Cft	
17	6/12 (i)	Fabrication of mild steel reinf or cement deformed bar cage of specified yield strength for R.C.C bored piles including cutting bending, lowering of cagewith crane in position, welding and fastening, including the cost of bindingwire, Cranemachine (also in cludes removal of rust from the bars) as approved and directed by the Engineer Incharge i) Grade-40	76.00 Kg	100/Kg	
18	11/35	Petty repair to main rooms.	3.00 Each	Each	
				Total A =	
Electric Work					
1	24/11	Supply and erection of single core PVC insulated copper conductor cables, in prelaidd PVC pipe/M.S. conduit/G.I pipe/wooden strip batten/wooden casing an capping/G.I. wire/trenches (rate for cables only):-			
	(i)	3/0.74 mm (3/0.029")	1320 Rft	P/Rft	
	(iii)	7/0.74 mm (7/0.029")	1550.00 Rft	P/Rft	
	(v)	7/1.12 mm (7/0.044")	295.00 Rft	P/Rft	
2	24/3	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries and repairing surface, etc., complete with all specials.			
	(ii)	20 mm i/d	350.00 Rft	P/Rft	
	(iii)	25 mm i/d	200 Rft	P/Rft	
3	24/106 (i)	Providing and fixing Pakistan Energy Label NEECA approved Copper winded wall bracket Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge. i) 18" Sweep dia	22.00 Each	Each	
4	24/44-i	Supply and erection of button holder. i) bakelite large size	40.00 Each	Each	
5	24/108 (iv)	P/F PVC double layer Switch kit Faceplate with specified switch holes i/c the cost of switches / sockets / dimmer made of Hi-Life / Bush / Schenider or approved equivalent manufacturer, screws complete as approved and directed by the Engineer Incharge. Three pin Light Plug 10/13 Amp	70.00 Each	Each	

The Islamia University of Bahawalpur

Construction of Partition with Brick Masonry at Law Department at Abbasia Campus

MRS, Jan to Jun 2025

No.	Ref.#	Description	Quantity	Unit Rate	Amount
6	24/110 (i)	P/F PVC concealed Switch kit Box i/c the cost of screws complete as approved and directed by the Engineer Incharge Small	90.00 Each	Each	
7	108 (iii)	P/FPVC double layer Switch kit Face plate with specified switch holes i/c the cost of switches/sockets/dimmer made of Legr and/ABB/Schenider or approved equivalent manufacturer, screws complete in all respect, as approved and directed by the Engineer Incharge (iii) 03 Gange	20.00 Each	Each	
8	105	Providing and fixing Pakistan Energy Label NEECA approved Copper wined Exhaust Fan i/c the cost of necessary cable and hardware for connection from ceiling rose complete as approved and directed by Engineer Incharge. b) Steel body (i) 12" sweep	3.00 Each	Each	
9	24/107 (iii)	Providing and fixing Pakistan Energy Label NEECA approved Copper wined Ceiling Fan i/c the cost of necessary cable and hardware for connection as approved and directed by Engineer Incharge. iii) 56" dia	7.00 Each	Each	
10	24/88 a(ii)	Suppling, Installation and comissioning of MCB (Miniature Circuit Breaker) of specified rating made of LEGRAND FRANCE/GEU.S.A/ SCHNEIDER GERMANY /SIEMEN GERMAN/TERASAKI JAPAN/ ABB SWITZERLAND or approved equivalent manufacturer in pre laid DBs and Panels i/c the cost of screws, necessary wire complete in all respect as approved and directed by the Engineer Incharge. a) Single Pole (ii) 6-40 Amp (6 KA)	12.00 Each	Each	
11	108 a(vi)	P/F PVC double layer Switch kit Face plate with specified switch holes i/c the cost of switches / sockets / dimmer made of Leg rand /ABB / Schenider or approved equivalent manufacturer ,screws complete in all respect, as approved and directed by the Engineer Incharge. a) One way Gange Switch (Small) (vi) Fan Dimmer	7.00 Each	Each	
12	N.S	Providing and Fixing LED Bulb 30 Watt i/c any accessories required at site. Complete in all respect as directed and approved by the Engineer Incharge (Pak Light (Made in Pakistan) or Equivalent)	30.00 Each	Each	
13	N.S	Supply & installation of PVC cable trunk (Duct) 16x25mm i/c any accessories (i.e. screw. Rawl plug or steel nail, etc.) as required at site. Complete in all respect as directed and approved by the Engineer Incharge (GM, Popular, Adamjee or Equivalent)	400.00 P/Rft	Rft	
				Total B =	
			Grand Total A+B=		



Executive Engineer (M)

The Islamia University of Bahawalpur

Special Renovation of Toilet Blocks For Students (Male & Female) at Old Campus Bahawalnagar.

Estimate Based on MRS Janu to June, 2025 BWN

No.	Description	Ref.	Quantity	Rate	Unit	Amount
Civil Work (Schedule Items)						
1	Dismantling 2nd class tile roofing	,4-22 b	255.00 Sft		%Sft	
2	Removing cement or lime plaster.	4-48	1157.32 Sft		%Sft	
3	Fabrication of mild steel Reinforcement for cement concrete including bending, laying in position, making joints and fastening i/c cast of binding wire and labour charges for bending of steel reinforcement also includes removal of rust from bars - Deformed Bar Grade 60	6/13-b	465.59 Kg		% Kg	
4	Providing and laying reinforced cement concrete (including prestressed concrete), using Ordinary Portland Cement / Sulphateresisting cement / Slag cement as may be required; coarse sand and screened graded and washed aggregate, in required shape and design, including forms, moulds, shuttering, lifting, compacting, curing, rendering and finishing exposed surface, complete (but excluding the cost of steel reinforcement, its fabrication and placing in position, etc.):- Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects. Ground Floor Ratio (1:1.5:3)	6/6-ai-2	127.50 Cft		Per Cft	
5	Dismantling cement concrete 1:2:4 plain.	,4/19c	7.20 Cft		% Cft	
6	Dry rammed brick or stone ballast, 1½" to 2" (40 mm to 50mm) gauge	,6/2	14.85 Cft		% Cft	
7	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): (f) Ratio 1: 2: 4	,6/5f	71.81 Cft		% Cft	
8	Pacca brick work in ground floor:- i) cement, sand mortar:- Ratio 1:4	7/5-i	3.00 Cft		% Cft	

The Islamia University of Bahawalpur

Special Renovation of Toilet Blocks For Students (Male & Female) at Old Campus Bahawalnagar.

Estimate Based on MRS Janu to June, 2025 BWN

No.	Description	Ref.	Quantity	Rate	Unit	Amount
9	Pacca brick work in first floor:- i) cement, sand mortar:- Ratio 1:5 First Floor	7/5-i+6i	47.63 Cft		% Cft	
10	Cement plaster 3/8" (10 mm) thick under soffit of R.C.C. roof slabs only, upto 20' height. Ratio 1:3 Ground Floor up to 20' height	11/10-b	180.00		% Sft	
11	Applying floating coat of cement 1/32" (0.8 mm) thick	,11/13	1337.32 Sft		% Sft	
12	Cement plaster 1:4 upto 20' (6.00 m) height: Upto 20' heights a) 1/2" (13 mm) thick	11/9-b	1157.32 Sft		% Sft	
13	Single layer of tiles 9"x4 1/2"x1 1/2" (225x113x40 mm) laid over 4"(100 mm) earth and 1" (25 mm) mud plaster without Bhoosa, grouted with cement sand 1:3 on top of RCC roof 'slab, provided with 34 lbs. per %Sft. or 1.72 Kg/Sq.mbitumen coating sand blinded.	9/5.	207.38 Sft		%Sft	
14	Supplying and laying polythene sheet over D.P.C. under floors and on roofs, etc 500 gauge (.005" thick)	26/39	207.38 Sft		Sft	
15	Providing and fixing mild steel chowkat of doors, windows, C.window, etc. including holdfast, making and threading holes for hinges, etc. complete:-M.S. angle iron 1 1/2"x 1 1/2"x 1/4" (40x40x6 mm) welded with M.S. flat 2"x 1/4" (50 mm x 6 mm)	,12/15 a	123.25 Sft		Sft	
16	Khuras on roof 2'x2'x6" (600 x 600 x 150 mm)	9/15.	1.00 No		Each	
17	Preparing surface and painting with emulsion paint:- New surface 3-coats	13/31. i+ii+ii	875.34 Sft		%Sft	
18	Priming coat of chalk under distemper.	11/22.	180.00 Sft		%Sft	
19	Distemping:- a) new surface:- iii) three coats	11/23.a.iii	180.00 Sft		%Sft	

The Islamia University of Bahawalpur

Special Renovation of Toilet Blocks For Students (Male & Female) at Old Campus Bahawalnagar.

Estimate Based on MRS Janu to June, 2025 BWN

No.	Description	Ref.	Quantity	Rate	Unit	Amount
20	Providing and laying superb quality Ceramic tiles dado of Master brand of specified size,Glossy/Matt/Texture skirting / dado of approved Color and Shade with adhesive bond over 1/2"thick (1:2) cemen tplaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharge.12"x18"/12"x24"/10"x24"/8"x24"/12"x36"	10/25.i	343.30 Sft		P/Sft	
21	Providing and laying superb quality Ceramic tile floors of Master brand of specified size,Glossy/Matt/Texture of approved Color and Shade as perapproved design with adhesive bond, over 3/4" thick(1;2) cement sand plaster i/c the cost of sealer for finishing the joints i/c cutting grinding complete in all respects and as approved and directed by the Engineer Incharge.12"x18"/12"x24"/10"x24"/8"x24"/12"x36"	10/24.i	176.32		Per Sft	
22	P/F 1-1/2" thick solid flush door comprising of 2.5 mm thick Commercially compressed over 2.5 mm thick commercial ply over 1" thick packing wood in style and rails under proper pressure i/c the cost of nails, tower bolt , handles, glue, sawing charges, Painting charges, sand papering and 3/8" thick matching wooden lipping as approved and directed by the Engineer Incharge	,12/50	37.24		Per Sft	
Civil Work (Non-Schedule Items)						
1	Providing & Fixing uPVC door 1.25" thick wooden colour i/c hinges kik plate, door handle with locking arrangement complete in all respects.	N/S	67.60		Per Sft	
2	Subsequent carriage of crushed stone aggregate total distance from Sargodha to Bahawalnagar IUB Campus at site of work average 278 KM	Lead Chart	170.29 Cft		%Cft	
Total						

The Islamia University of Bahawalpur

Special Renovation of Toilet Blocks For Students (Male & Female) at Old Campus Bahawalnagar.

Estimate Based on MRS Janu to June, 2025 BWN

No.	Description	Ref.	Quantity	Rate	Unit	Amount
	<u>Electric Work (Schedule Items)</u>					
1	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries, and repairing surface, etc., complete with all specials.					
	i) 20 mm i/d	24/3-ii	83		Per Rft	
	ii) 25 mm i/d	24/3-iii	34.00		Per Rft	
			Rft			
2	Supply and erection of single core PVC insulated copper conductor cables, in prelaid PVC pipe/M.S. conduit/G.I pipe/wooden strip batten/wooden casing an capping/G.I. wire/trenches (rate for cables only). a) 250/440 volts, PVC insulated:					
	i) 3/0.74 mm (3/0.029")	24/11-a-i	236.00		Per Rft	
	ii) 7/0.74 mm (7/0.029")	24/11-a-iii	267.00		Per Rft	
			Rft			
3	Providing and fixing Pakistan Energy Label NEECA approved Copper wined Exhaust Fan i/c the cost of necessary cable and hardware for connection from ceiling rose complete as approved and directed by Engineer Incharge .Plastic body (i) 10" dia	24/105.a.i	2.00		Each	
			No			
4	P/F PVC double layer Switch kit Faceplate with specified switch holes i/c the cost of switches / sockets / dimmer made of Hi-Life / Bush / Schenider, screws complete as approved and directed by the Engineer Incharge	24/108.b	2.00		Each	
	Large		No			
	05 Gange		No			
5	P/F PVC concealed Switch kit Box i/c the cost of screws complete as approved and directed by the Engineer Incharge	24/110	2.00		Each	
	ii) Large		No			
6	Supply and erection of ceiling rose, bakelite	24/35	2.00		Each	
			No			
					Total	

The Islamia University of Bahawalpur

Special Renovation of Toilet Blocks For Students (Male & Female) at Old Campus Bahawalnagar.

Estimate Based on MRS Janu to June, 2025 BWN

No.	Description	Ref.	Quantity	Rate	Unit	Amount
	<u>Electric Work (Non-Schedule Items)</u>					
1	Supply & installation of LED 24 W (8 Inch) Down Light 6500 K ,2000 Lumen (Surface Mounted, 220V~) i/c any accessories required at site. Complete in all respect as directed and approved by the Engineer Incharge (Philips Essential or Equivalent)	NS	6.00 No		Each	
					Total	
	<u>Plumbing Work (Schedule Items)</u>					
1	Providing ,fixing testing and commissioning of μ-PVC (Unplasticized polyvinyl Chloride) Nikasi /waste pipe make of dadex /Popular /Beta/BBJ plain/ socket ended conforming to code EN-1401 of specified SDR (Standard Dimension Ratio) including thecost of specials and Solvents complete in all respect as approved and directed by the Engineer Incharge.Type (SDR 32.5/SN-8)	,19/47	137.00 Rft		P/Rft	
2	Providing, fixing, testing and commissioning of μ-PVC (Unplasticized polyvinyl Chloride) Nikasi /wastepipe Fittings make of dadex /Popular /Beta/ BBJ conformingto code EN-1401 including thecost of Solvents complete in all respect as approved and directed by the Engineer Incharge.	19/49.	13.00 No		Each	
3	'Providing and fitting glazed earthen ware water closet squatter type (Orissa pattern) combined with foot rest. (Coloured).	19/4-ii.	5.00 No		Each	
4	Providing and fitting glazed earthen ware wash hand basin 56x40 cm (22"x16") including bracket set, waste pipe and waste coupling, etc. i. coloured, with pedestal	19/7ii.	5.00 No		Each	

The Islamia University of Bahawalpur

Special Renovation of Toilet Blocks For Students (Male & Female) at Old Campus Bahawalnagar.

Estimate Based on MRS Janu to June, 2025 BWN

No.	Description	Ref.	Quantity	Rate	Unit	Amount
5	Providing, laying, testing and commissioning of POLY PROPYLENE RANDOM COPOLYMER (PPRC) water supply pipe made of (Dadex/Popular/Beta/BBJ) with specified pressurating PN (PRESSURE NOMINAL) and conforming to DIN 8077-8078 code i/c cost of solvent, specials ,making jharries complete in all respectas approved and directedby Engineer Incharge.(Internal/External Diameters mentioned).	23/47.bii				
	PN-20 pipe					
	ii)(3/4") 25 mm		102.20		P/Rft	
	iii)(1") 32 mm		125.00		P/Rft	
				Rft		
6	Providing and Fixing Crommium plated bib cock 1/2" dia.	19/27.ii	5.00		Each	
				Nos		
7	Providing and fixing chromium plated pillar-cock, heavy:-					
	ii) (1/2")	19/24.ii	5.00		Each	
				No.		
8	Providing and fixing chromium plated tee stop cock '15mm (½").	19/28	10.00		Each	
				No		
9	Providing and fitting plastic made low down flushing cistern 13.63 litre (3 gallons) capacity, including bracket set, copper connection, etc. complete. ii) coloured	19/13.ii	5.00		Each	
				No.		
10	Providing and Fixing of SS 304 Floor Drain ,complete in all respect as approved and directed by Engineer Incharge.	Replaceme nt items- 19/12.ii	7.00		Each	
				No		
11	Providing and fixing Bathroom Accessories (7-piece set) Master brand - One Cosmetic Shelf, One Towel rod with bracket, One soap dish, One double hook, One towel ring, brush holder, toilet paper holder & looking glass i/c the cost of hardwares etc complete in all respect as approved and directed by the Engineer Incharge.	19/23				
	i) Plastic soap dish		5.00		Each	
	ii) Plastic toilet paper holder		5.00		Each	
	iii) Plastic tower rail		2.00		Each	

The Islamia University of Bahawalpur
Special Renovation of Toilet Blocks For Students (Male & Female) at Old Campus Bahawalnagar.

Estimate Based on MRS Janu to June, 2025 BWN

No.	Description	Ref.	Quantity	Rate	Unit	Amount
			No			
12	Providing and hoisting vertical/ horizontal type storage tank of required capacity made of rotationally molded from (HDPE), double ply polyethelene of approved manufacturer i/c cost of making connection for inlet/outlet pipe, float valve i/c all cost of specials& labour complete in all respect as approved and directed by the Engineer Incharge.	19/51	1000.00 Gallon		Per Gallon	
					Total	
	<u>Plumbing Work (Non-Schedule Items)</u>					
1	Providing & Fixing Looking Glass 5 mm thick with sides Plastic Gola imported quality, complete in all respects and as approved by the Engineer Incharge.	NS	11.06 Sft		P/ Sft	
2	Providing & Fixing of Golden Electric Pump 0.5 H.P ,Size 1.25"x1" for Water supply including connection & testing with electric pump in working condition, complete in all respects, as approved by the Engineer Incharge.	NS	1.00 No		Each	
					Total	



Executive Engineer (M)