

The Islamia University of Bahawalpur

1 Construction of Footpath and Tuff Tile Pavement at Baghdad-ul-Jadeed Campus

A about to Agriculture College
at Baghdad-ul-Jadeed Campus

Civil Work

MRS Jul-Dec, 2019

No	MRS	Description	Quantity	Rate	Unit	Amount
1	3/52	Earthwork in excavation of drains, irrigation channels through excavator / drag lines in all kind of soil and conditions(dry,wetslush,daldal and under water) including its disposal and preparation of working pad for operation of machinery. (Rates including 100 ft lead)	96.00	Cft	%o Cft	
2	6/3d	Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth: Ratio 1:6:12	4998.00	Cft	% Cft	
3	7/4	Pacca brick work in foundation & plinth with cement sand mortar (1:6)	100.00	Cft	% Cft	
4	3/5iii +17	Earthwork in ordinary soil for embankments lead upto 100 ft. (30 m), including ploughing and mixing with blade grade or disc harrow or other suitable equipment, and compaction by mechanical means at optimum moisture content and dressing to designed section, complete in all respects:- 85% maximum modified AASHO dry density. Lead upto ¼ mile (400 m).	45000.00	Cft	%o Cft	
5	11/11	Cement plaster 1:5 upto 20' (6.00 mm) height:- ½" (13 mm) thick	144.00	Sft	% Sft	
6	6/5f	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	625.00	Cft	% Cft	
7	10/43 b	Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. Complete in all respect. (50% Grey / 50% Coloured) 60 mm thick	15000.00	Sft	Per Sft	
Total						

Civil Work (Non-Schedule)

No		Description	Quantity		Unit	
1	N.S	Providing & Fixing Pre-Cast Kerb stone size 12"x14"x6" (300mmx350mmx150mm) and duly embedded on bed of PCC 1:4:8 (4" thick), PCC 1:2:4 under kerb stone 3" thick and hanuching concrete 1:2:4 i/c painting of 3 coats complete in all respects as per design & as approved by the engineer incharge made (Izhar/Banu Mukhtar/ Mukhtar Sons)	2500.00	Rft	Per Rft	
2	N.S	Providing & Fixing Pre-Cast Kerb stone size 12"x12"x4" (300mmx300mmx100mm) and duly embedded on bed of PCC 1:4:8 (4" thick), PCC 1:2:4 under kerb stone 3" thick and hanuching concrete 1:2:4 complete in all respects as per design & as approved by the engineer incharge made (Izhar/Banu Mukhtar/ Mukhtar Sons)	2500.00	Rft	Per Rft	
Total						

No	MRS	Description	Quantity	Rate	Unit	Amount
----	-----	-------------	----------	------	------	--------

B Widening & Tuff Paver of Path From Girls Hostels to Main Approach Road at Baghdad-ul-Jadeed Campus
Civil Work

MRS Jul-Dec, 2019

No	MRS	Description	Quantity	Rate	Unit	Amount
1	3/52	Earthwork in excavation of drains, irrigation channels through excavator / drag lines in all kind of soil and conditions(dry,wetslush,daldal and under water) including its disposal and preparation of working pad for operation of machinery. (Rates including 100 ft lead)	2600.00		Cft	%o Cft
2	6/3d	Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth: Ratio 1:6:12	858.00		Cft	% Cft
3	7/4	Pacca brick work in foundation & plinth with cement sand mortar (1:6)	60.00		Cft	% Cft
4	11/11	Cement plaster 1:5 upto 20' (6.00 mm) height:- ½" (13 mm) thick	60.00		Sft	% Sft
5	6/5f	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	325.00		Cft	% Cft
6	13/5	Painting new surface: Preparing surface and painting of doors and windows any type (including edges):- 3 Coats	1300.00		Sft	% Sft
7	10/43 b	Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. Complete in all respect. (50% Grey / 50% Coloured) 60 mm thick	6500.00		Sft	Per Sft
						Total

Civil Work (Non-Schedule)

No	MRS	Description	Quantity	Rate	Unit	Amount
1	N.S	Providing & Fixing Pre-Cast Kerb stone size 12"x12"x4" (300mmx300mmx100mm) and duly embedded on bed of PCC 1:4:8 (4" thick), PCC 1:2:4 under kerb stone 3" thick and hanuching concrete 1:2:4 complete in all respects as per design & as approved by the engineer incharge made (Izhar/Banu Mukhtar/ Mukhtar Sons)	1300.00		Rft	Per Rft
						Total

C Providing & Laying Tuff Paver East Side of Main Auditorium Building at Baghdad-ul-Jadeed Campus
Civil Work

MRS Jul-Dec, 2019

No	MRS	Description	Quantity	Rate	Unit	Amount
1	3/52	Earthwork in excavation of drains, irrigation channels through excavator / drag lines in all kind of soil and conditions(dry,wetslush,daldal and under water) including its disposal and preparation of working pad for operation of machinery. (Rates including 100 ft lead)	400.00		Cft	%o Cft
2	6/3d	Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth: Ratio 1:6:12	4323.00		Cft	% Cft

No	MRS	Description	Quantity	Rate	Unit	Amount
3	7/4	Pacca brick work in foundation & plinth with cement sand mortar (1:6)	300.00		Cft	% Cft
4	11/11	Cement plaster 1:5 upto 20' (6.00 mm) height:- ½" (13 mm) thick	300.00		Sft	% Sft
5	6/5f	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	90.00		Cft	% Cft
6	3/5iii +17	Earthwork in ordinary soil for embankments lead upto 100 ft. (30 m), including ploughing and mixing with blade grade or disc harrow or other suitable equipment, and compaction by mechanical means at optimum moisture content and dressing to designed section, complete in all respects:- 85% maximum modified AASHO dry density. Lead upto ¼ mile (400 m).	16700.00		Cft	%o Cft
7	10/43 b	Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. Complete in all respect. (50% Grey / 50% Coloured) 60 mm thick	13100.00		Sft	Per Sft
						Total

Civil Work (Non-Schedule)

No	MRS	Description	Quantity	Rate	Unit	Amount
1	N.S	Providing & Fixing Pre-Cast Kerb stone size 12"x12"x4" (300mmx300mmx100mm) and duly embedded on bed of PCC 1:4:8 (4" thick), PCC 1:2:4 under kerb stone 3" thick and hanuching concrete 1:2:4 complete in all respects as per design & as approved by the engineer incharge made (Izhar/Banu Mukhtar/ Mukhtar Sons)	360.00		Rft	Per Rft
						Total

D Providing & Laying Tuff Paver on Path in Front of Central Library & Faculty of Arts at Baghdad-ul-Jadeed Campus

Civil Work

MRS Jul-Dec, 2019

No	MRS	Description	Quantity	Rate	Unit	Amount
1	3/52	Earthwork in excavation of drains, irrigation channels through excavator / drag lines in all kind of soil and conditions(dry,wetslush,daldal and under water) including its disposal and preparation of working pad for operation of machinery. (Rates including 100 ft lead)	720.00		Cft	%o Cft
2	6/3d	Cement concrete brick or stone ballast 1½ " to 2" (40 mm to 50 mm) gauge, in foundation and plinth: Ratio 1:6:12	330.00		Cft	% Cft
3	7/4	Pacca brick work in foundation & plinth with cement sand mortar (1:6)	360.00		Cft	% Cft
4	11/11	Cement plaster 1:5 upto 20' (6.00 mm) height:- ½" (13 mm) thick	360.00		Sft	% Sft
5	6/5f	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): Ratio 1:2:4	195.00		Cft	% Cft

No	MRS	Description	Quantity	Rate	Unit	Amount
6	13/5	Painting new surface: Preparing surface and painting of doors and windows any type (including edges):- 3 Coats	1560.00		% Sft	
7	10/43 b	Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. Complete in all respect. (50% Grey / 50% Coloured) 60 mm thick	7800.00		Per Sft	
					Total	

Civil Work (Non-Schedule)

No		Description	Quantity	Rate	Unit	Amount
1	N.S	Providing & Fixing Pre-Cast Kerb stone size 12"x12"x4" (300mmx300mmx100mm) and duly embedded on bed of PCC 1:4:8 (4" thick), PCC 1:2:4 under kerb stone 3" thick and hanuching concrete 1:2:4 complete in all respects as per design & as approved by the engineer incharge made (Izhar/Banu Mukhtar/ Mukhtar Sons)	1560.00		Per Rft	
					Total	

No	MRS	Description	Quantity	Rate	Unit	Amount
----	-----	-------------	----------	------	------	--------

The Islamia University of Bahawalpur

2 Providing & Fixing of Direction Board for Different Places at Baghdad-ul-Jadeed Campus

Civil Work (Non-Schedule)

No.	Description	Quantity	Rate	Unit	Amount
1	Providing and fixing Direction boards 5'x3' with sigle plate consisting of G.I pipe 2" dia Light Quality for frame, 1" dia G.I pipe for spacer including 1.50"x1.50"x1/4" M.S angle iron and G.I sheet 1/8" thick with painting and Lettering with reflector and 3" dia G.I pipe Light quality for legs embedded in cement concrete 1:2:4 complete in all respect as per design, drawing & pattern and as approved by the engineer incharge.	15.00	No	Each	
2	Providing and fixing small Direction boards arrow style consisting of G.I pipe 2" dia Light Quality for legs and G.I sheet 1/8" thick with painting and Lettering with reflector and embedded in cement concrete 1:2:4 complete in all respect as per design, drawing & pattern, as approved by the engineer incharge.	39.00	No	Each	
3	Providing and fixing Direction boards with 6 No. plates consisting of G.I pipe 3" dia Light Quality for legs and G.I sheet 1/8" thick with painting & Lettering with reflector and embedded in cement concrete 1:2:4 complete in all respect as per design, drawing & pattern, as approved by the engineer incharge	7.00	No	Each	
4	Providing and fixing Direction boards with 4 No. plates consisting of G.I pipe 3" dia Light Quality for legs and G.I sheet 1/8" thick with painting and Lettering with reflector and embedded in cement concrete 1:2:4 complete in all respect as per design, drawing & pattern and as approved by the engineer incharge.	1.00	No	Each	
5	Providing and fixing Direction boards with 3 No. plates consisting of G.I pipe 3" dia Light Quality for legs and G.I sheet 1/8" thick with painting and Lettering with reflector and embedded in cement concrete 1:2:4 complete in all respect as per design, drawing & pattern and as approved by the engineer incharge.	1.00	No	Each	
				Total	

No	MRS	Description	Quantity	Rate	Unit	Amount
----	-----	-------------	----------	------	------	--------

The Islamia University of Bahawalpur

3 Annual Special Repair for Cat-C House No. C-8 at Baghdad-ul-Jadeed Campus

MRS (Jul to Dec) 2019

No.	RS R	Description	Quantity	Unit Rate	Unit	Amount
Annual Repair						
1	4/49-b	Scraping Ordinary distemper, oil bound distemper, or paint of wall.	3,747.90 Sft		% Sft	
2	11/36	Petty repair to small room	4.00 Nos		Each	
3	3/31-i	Preparing surface and painting with emulsion paint:- old surface 2 coats	6,052.84 Sft		% Sft	
4	3/4-c-i	Painting Doors & Windows any type on old surface 2 Coats.	2,193.26 Sft		% Sft	
5	3/32A	Providing and Applying of weather sheild paint of approved quality on external surface of building i/c preparation of surface application of primer complete in all respect old surface	5541.13 Sft		% Sft	
			Total			
Civil Work						
1	4/20	Dismantling cement concrete reinforced, separating reinforcement from concrete, cleaning and straightening the same.	161.49 Cft		% Cft	
2	4/48	Removing cement or lime plaster.	2166.87 Sft		% Sft	
3	7/5-i	Pacca brick work in ground floor:- Cement, sand mortar:- Ratio 1:5	647.52 Cft		% Cft	
4	1/11-i	Cement plaster 1:5 upto 20' (6.00 m) height:- ½" (13 mm) thick	2488.87 Sft		% Sft	
5	11/6-ii	Providing and laying machine sprayed plaster ½" (13 mm) thick, using cement and chips zero gauge, over the existing plastered and roughened surface, upto 20' (6.00 m) height. ratio 1:2	252.50 Sft		% Sft	
6	10/25	Laying floor of approved coloured glazed tiles ¼ "(6 mm) thick, laid in white cement and pigment on a bed of ¾" (20 mm) thick cement mortar 1:2.	74.72 Sft		% Sft	
7	10/38	Coloured glazed tile dado ¼" (6mm) thick in pigment over 1:2 cement, sand mortar ¾"(20mm) thick, including finishing.	385.00 Sft		% Sft	
8	6/6	(a) (i) Reinforced cement concrete in roof slab, beams, columns lintels, girders and other structural members laid in situ or precast laid in position, or prestressed members cast in situ, complete in all respects:- (3) (c) Type C (nominal mix 1: 2: 4)	18.75 Cft		P/Cft	
9	6/9-b	Fabrication of mild steel reinforcement for cement concrete, including cutting, bending, laying in position, making joints and fastenings, including cost of binding wire and labour charges for binding of steel reinforcement (also includes removal of rust from bars) deformed bar	30.26 Kg		% Kg	
10	0/15-	Providing and laying topping of cement concrete 1:2:4, including surface finishing and dividing in panels:- 2"(50 mm) thick	325.00 Sft		% Sft	

No	MRS	Description	Quantity	Rate	Unit	Amount
11	12/50	Providing and fixing 1½" (40mm) thick solid flush door shutter sterling or equivalent with commercial ply (5 mm thick) on both sides double pressed and deodar wood lipping 1½"x3/8" (40mm x 10mm) around shutter including chromium plated fitting, iron hinges with aluminium kick plate 22 SWG on both sides & finger plate complete in all respect.	45.50 Sft		P/Sft	
12	2/12-b	First class deodar wood wrought joinery work in wire gauze doors and windows, with 22 SWG G.I. wire gauze, 12x12 meshes per square inches (5x5 per cm2) including iron fittings etc. complete:- Deodar wood framing 1½" (40 mm) thick, with wire gauze fixed in position:- ii) with springs or spring hinges	45.50 Sft		P/Sft	
13	12/45	Glazing with panes (24 oz. to 26 oz.), using putty and deodar wooden fillets.	16.00 Sft		P/Sft	
14	0/43-	Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope complete in all respect. (50% Grey / 50% Coloured) 60-mm thick	1768.25 Sft		P/Sft	
			Total			
<u>Civil Work Non-Schedule</u>						
1	N.S	Providing and laying Floor Tile 16" x 16" Granite effect, (Master) GEM series Polished (Dark color) ST) including 05% Wastage laid in white cement and pigment on a bed of ¾" thick cement mortar 1:2 complete in all respects as approved by Engineering incharge.	1829.63 Sft		P/Sft	
2	N.S	Providing and fixing ¾" thick Laminated Board shutter with ¾" x ¾" deodar wood beading wardrobe frame of 3"x1.5" M.S Box pipe 18 SWG including tower bolts on top & bottom lock 808, hinges, Sprite polish complete in all respects including aluminium hanger rod etc. as approved by the Engineer Incharge.	55.75 Sft		P/Sft	
			Total			
<u>Electric Work Schedule</u>						
1	24/31-	Supply and erection of switches 5 Amp. Piano type	12.00 Nos		Each	
			Total			
<u>Electric Work N.S</u>						
1	N.S	Supply, installation connection of Plastic Wall Light, water tight shade & cover i/c 12W LED bulb (Day light E-27 Orient) and any accessories required at site. Complete in all respect as approved by the engineer incharge. N.S	6.00 Nos		Each	
2	N.S	Supply and ersion of energy saver 23/25 watt Philips complete in all respect as approved by the engineer incharge	8.00 Nos		Each	
3	N.S	Supply and erection of fan Dimmer KM complete in all respects as approved by the Engineer incharge	5.00 Nos		Each	
			Total			
<u>Plumbing Work</u>						
1	19/3-ii	Providing and fitting glazed earthen ware water closet, squatter type (Orisa pattern), combined with foot rest. Coloured	1.00		Each	

No	MRS	Description	Quantity	Rate	Unit	Amount
2	9/34-	Providing and fitting "P" trap:- 10 cm (4") glazed.	4.00		Each	
3	19/27	Providing and fixing chromium plated tee stop cock '15mm (½").	4.00		Each	
4	19/29	Providing and fixing, chromium plated mixing valve, for wash hand basin, sink or shower.	No			
5	9/26-	Providing and fixing chromium plated bib cock:- 1.5 cm (½")	2.00		Each	
6	19/22	Providing and fitting:-	No			
i		plastic soap dish	2.00		Each	
ii		plastic toilet paper holder	No			
iii		plastic towel rail	2.00		Each	
iv		plastic shelf 60x13 cm (24"x5") with bracket and railing.	No			
7	19/19	Providing and fixing looking glass 55x40 cm (22"x16") size, and 5 mm thick, first quality.	2.00		Each	
8	19/28	Providing and fixing chromium plated shower rose:- 1.5x10 cm (½"x4")	No			
9	19/1	Replacement Providing and fixing, chromium plated waste coupling:- 3 cm (1¼")	2.00		Each	
10	19/3	Providing and fixing, waste pipe of PVC:- 3 cm (1¼")	No			
			TOTAL	=		
1	N.S	<u>Plumbing Work Non-Schedule Items</u> Providing and fixing and testing uPVC plain ends socketed pipes, waste, vent & rain water as per approved make and quality including uPVC fittings with solvent cement jointing or rubbering joints complete in all respects including clamps, tee etc complete in all respect as approved by the engineer incharge 4" i/d	50.00		P/Rft	
2	N.S	Providing and laying, cutting, jointing, testing and disinfecting PPRC pipe line for hot and cold water supply complete in all respect socket, elbow, encaps, male/female, threaded, fitting, like teese, adoptors to connect polydex pipes to other pipe and shower, wash basin, bibcock etc. as required at site. 25mm o/d (Dadex/Beta/BBJ)	70.00		P/Rft	
3	N.S	Providing and laying, cutting, jointing, testing and disinfecting PPRC pipe line for hot and cold water supply complete in all respect socket, elbow, encaps, male/female, threaded, fitting, like teese, adoptors to connect polydex pipes to other pipe and shower, wash basin, bibcock etc. as required at site. 32mm o/d (Dadex/Beta/BBJ)	Rft			
4	N.S	Providing & Fixing Stop Valve PPRC 25mm complete in all respects, as approved by the Engineer Incharge.	100.00		P/Rft	
5	N.S	Providing & Fixing Stop Valve PPRC 32mm complete in all respects, as approved by the Engineer Incharge.	Rft			
			4.00		Each	
			No			
			2.00		Each	
			No			

No	MRS	Description	Quantity	Rate	Unit	Amount
6	N.S	Providing & Fitting plastic floor jali best quality complete in all respect as per specifications and drawings and as approved by the Engineer Incharge.	3.00 No		Each	
7	N.S	Providing & Fixing Muslim shower with double bib cock of Fasial / Master with flexibe pipe complete unit in working condition, complete in all respect as per specifications and drawings and as approved by the Engineer Incharge.	2.00 No		Each	
8	N.S	Providing and fixing Coloured Glazed Earthen ware water closet Europen type Couple set including Flush Tank fixed with comode, Bakelite sheet cover thrimble, connection pipe Complete in all respect and approved by Engineering Incharge. (Master Company)	1.00 No		Each	
9	N.S	Providing & Fixing wall shower (Dilawar) complete in all respects as approved by the Engineer Incharge.	1.00 No		Each	
			TOTAL	=		

No	MRS	Description	Quantity	Rate	Unit	Amount
----	-----	-------------	----------	------	------	--------

4

The Islamia University of Bahawalpur
Renovation of G.M. Ghotvi Hall at Abbasia Campus

MRS July - Dec 2019

No.	Description	Quantity	Unit Rate	Unit	Amount
Civil work (Non-Schedule)					
1	Dismantling of old false ceiling and cleaning the site at 2nd floor with Extra height as per direction by the Engineer incharge.	2416.31	Sft	P/Sft	
2	Providing & fixing false ceiling of Gypsum 9mm thick complete in all respects and as approval of sample by the Engineer incharge.	2416.31	Sft	P/Sft	
3	Providing & Fixing PVC coloured wall panelling 10" x 9.5' including gola border colored vertically fixed with steel nail, complete in all respect and as approved by the Engineer Incharge	1928.50	Sft	P/Sft	
TOTAL					
Electric work (Schedule Item)					
1	Supply and erection of single core PVC insulated copper conductor cables, in pre-laid PVC pipe/M.S. conduit/G.I pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only). i) 3/0.74 mm (3/0.029")	1280.00	Rft	P/Rft	
2	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries, and repairing surface, etc., complete with all specials. iii) 25 mm i/d	150.00	Rft	P/Rft	
TOTAL					
Electric Work (Non-Schedule)					
1	Supply, installation & connection of LED (SMD) Ceiling Light (open type) 12-w(220V-day light) round shape i/c any accessories (Phillips) 1 year warranty required at site. Complete in all respect as approved by the engineer incharge.	80.00	No.	Each	
2	Providing & Fixing China Sheet with switches (Futina, Klass or Hi-Life) and underground PVC box complete in all respects as per approved design and sample and as directed by the Engineer incharge. 8 switches + 2 socket	4.00	Nos.	Each	
TOTAL					

No	MRS	Description	Quantity	Rate	Unit	Amount
----	-----	-------------	----------	------	------	--------

The Islamia University of Bahawalpur

5 Providing & Fixing Gypsum False Ceiling for PRO office at Abbasia Campus

MRS July - Dec 2019

No.	Description	Quantity	Unit Rate	Unit	Amount
<u>Civil work (Schedule)</u>					
1	Preparing surface and painting with emulsion paint:- 2 Coats	1672.00	Sft	%Sft	
2	Painting old surfaces:- Painting doors and windows, any type: 2 Coats	260.50	Sft	%Sft	
TOTAL					
<u>Civil work (Non-Schedule)</u>					
1	Providing & fixing false ceiling of Gypsum 9mm thick complete in all respects and as approval of sample by the Engineer incharge.	136.00	Sft	P/Sft	
2	Providing & Fixing PVC coloured wall panelling 10" x 9.5' including gola border colored vertically fixed with steel nail, complete in all respect and as approved by the Engineer Incharge	465.50	Sft	P/Sft	
TOTAL					
<u>Electric work (Schedule Item)</u>					
1	Supply and erection of single core PVC insulated copper conductor cables, in pre-laid PVC pipe/M.S. conduit/G.I pipe/wooden strip batten/wooden casing and capping/G.I. wire/trenches (rate for cables only). i) 3/0.74 mm (3/0.029")	301.00	Rft	P/Rft	
2	Supply and erection of PVC pipe for wiring recessed in walls, including inspection boxes, pull boxes, hooks, cutting jharries, and repairing surface, etc., complete with all specials. iii) 25 mm i/d	30.00	Rft	P/Rft	
TOTAL					
<u>Electric Work (Non-Schedule)</u>					
1	Supply, installation & connection of LED (SMD) Ceiling Light (open type) 12-w(220V-day light) round shape i/c any accessories (China made) 1 year warranty required at site. Complete in all respect as approved by the engineer incharge.	10.00	No.	Each	
2	Providing & Fixing China Sheet with switches (Futina, Klass or Hi-Life) and underground PVC box complete in all respects as per approved design and sample and as directed by the Engineer incharge. 8 switches + 2 socket	1.00	Nos.	Each	
TOTAL					